TESTING 765 kV EXTRA HIGH-VOLTAGE EQUIPMENT

Qualifying the next generation of extra-high-voltage transmission equipment - a laboratory and standards-based framework

Powertech | August 2026 | Public/External Distribution

TECHNICAL INQUIRIES	BUSINESS DEVELOPMENT INQUIRIES
Sara Tahermaram, P.Eng Division Manager, Power Utility Laboratory Services **Email:** sara.tahermaram@powertechlabs.com	**Reesha Parmar** Senior Manager, Business Development & Marketing **Email:** reesha.parmar@powertechlabs.com

Disclaimer: This whitepaper is provided for informational purposes only and does not constitute a specification, engineering advice, or a binding offer. Applicable contract documents, utility specifications, and referenced standards shall govern in the event of any conflict. Test programs, acceptance criteria, and results depend on the equipment configuration, test setup, and project-specific requirements.

ABSTRACT

As renewable integration, electrification, data center growth, and aging-infrastructure reinvestment place new demands on the grid, utilities worldwide are revisiting extra-high-voltage (EHV) transmission up to 765 kV as a way to move power over long distances — with lower losses and fewer new transmission corridors than lower-voltage alternatives. That shift delivers real system-level benefits, but it also introduces qualification challenges that go beyond conventional high-voltage testing practices.

At 765 kV, increased electrical clearances, stronger electric-field effects (including corona and ionization), higher impulse energy requirements, and tighter diagnostic noise limits place new demands on both equipment manufacturers and independent test laboratories.

This whitepaper summarizes the testing considerations that most often govern the successful qualification of EHV 765 kV transmission components. This includes power-frequency withstand (dry/wet), lightning and switching impulse performance, partial discharge (PD) diagnostics, corona/radio influence voltage (RIV) evaluation, short-time withstand current tests, temperature-rise tests , conductor stress-strain and creep testing and mechanical tensile and cantilever testing.

The paper also discusses how commonly referenced IEC/IEEE/ANSI standards and utility specifications interact in practice, and highlights the importance of traceable, ISO/IEC 17025-compliant measurement systems in supporting acceptance decisions for procurement, regulatory oversight, and long-term system reliability. From the perspectives of utilities, regulators, manufacturers, and engineering, procurement, & construction companies (EPCs), the intent is to support early alignment on standards interpretation, test scope, witnessing, and reporting requirements to reduce redesign risk, schedule impacts, and in-service failure exposure.

KEY TAKEAWAYS

- Operation at 765 kV drives significant changes in transmission system component geometries and physical design to manage electric-field stresses.
- Qualification testing of these designs requires substantially larger laboratory setups, including increased conductor lengths, to control corona and air ionization effects.
- Test outcomes depend on early alignment between IEC, IEEE, and ANSI standards and utility-specific specifications, particularly for methods and acceptance criteria.
- Comprehensive electrical qualification commonly includes power-frequency withstand testing (dry and wet), lightning and switching impulse performance, partial discharge diagnostics, and corona and radio influence voltage evaluation
- Confidence in test results is strengthened with the use of independent laboratories with traceable ISO/IEC 17025-accredited measurement and calibration practices.

Early agreement on acceptance criteria, witnessing, and reporting expectations reduces the risk of late-stage redesigns and schedule impacts.

AUDIENCE

Electric Utilities: Owners and operators planning new 765 kV assets or updates require confidence in equipment performance under expected service conditions.

Regulators and System Operators: Stakeholders who require objective evidence of compliance, traceability, and measurement rigor for critical grid infrastructure.

Manufacturers and EPCs: Teams responsible for qualification, factory acceptance, and project handover who need timely, repeatable results and clear reporting.

Typical Deliverables (Reporting Package)

- Test plan(s) conforming to IEC/IEEE/ANSI and utility specifications.
- Instrumentation list with ISO/IEC 17025 calibration traceability and stated measurement uncertainties.
- Documented test results, including details of test setup, test data, waveforms, and acceptance determination.
- Final test report suitable for procurement, acceptance, and regulatory review, signed and

WHY 765kV TESTING IS DISTINCT

Transmission systems that have supported reliable service for decades are being asked to accommodate a new generation of demands, including utility-scale renewable integration, industrial and transportation electrification, rapid growth in data center loads, and reinvestment in aging infrastructure. These pressures are driving interest in 765 kV transmission as a practical way to expand regional power transmission capabilities while reducing losses and limiting the number of additional corridors required.

765 kV is a major step in bulk power transmission, enabling efficient transfer of large power blocks over long distances. It also introduces electrical stress and physical dimensions that materially change how equipment must be tested and how results should be interpreted.

Consequences of failure at 765 kV can affect regional reliability and involve high outage and replacement costs. Qualification programs require purpose-built facilities, experienced test engineering, and measurement practices that are traceable and repeatable.

- **Electric-field effects:** higher field intensities increase sensitivity to corona, air ionization, and surface conditions, affecting both performance and measurement.
- **Clearances and scale:** larger phase-to-phase and phase-to-ground distances, plus multi-meter insulation assemblies, can exceed the space available in conventional high voltage labs.
- **Impulse requirements:** lightning and switching impulse levels demand high-energy equipment, controlled wave-shaping, and verified measurements.
- **Wet testing and environment:** controlled rain, humidity, and temperature can be necessary to demonstrate withstand margins and identify critical conditions.
- **Low-noise diagnostics:** partial discharge and RIV/corona measurements require low-background environments and well-characterized uncertainty.

For stakeholders, the objective is not only to complete prescribed tests, but to generate evidence that supports procurement decisions, acceptance documentation, and—where applicable—regulatory review.

COMMON CHALLENGES IN 765 kV QUALIFICATION TESTING

Challenges in 765 kV qualification testing vary by equipment type and project requirements. The considerations below highlight several common factors that can affect test planning and execution, but do not represent a complete list.

- Laboratory facility clearances and geometry constraints can limit representative setups or full-scale assemblies.
- Achieving required impulse wave-shape control becomes more challenging at higher energy levels, particularly for switching impulses.
- Elevated background noise can reduce PD measurement sensitivity and affect result interpretation.
- Corona/RIV results become highly dependent on conductor length and geometry if test setups are not representative.
- Wet-test repeatability can vary without controlled rain rate, water conductivity, and environmental conditions.
- Misalignment between IEC/IEEE requirements and utility specifications can lead to ambiguity in acceptance decisions.
- Late-stage test failures may result in redesign and cascading schedule impacts.

STANDARDS AND TEST FRAMEWORK

Qualification testing for 765 kV equipment is typically performed in accordance with IEC and IEEE high-voltage test technique standards, supplemented by relevant ANSI documents and utility-specific specifications. At EHV levels, laboratories often document justified adaptations in test set-up geometry, measurement approach, and noise control to ensure tests remain representative and results are technically defensible.

Consistent technical interpretation of these standards is essential to support acceptance decisions, particularly where utility requirements introduce additional constraints on test methods, acceptance criteria, witnessing, or reporting.

TYPICAL 765kV COMPONENTS TESTED (NOT LIMITED TO)

- Gas Insulated Switchgear (GIS), Circuit Breakers (CBs) and disconnects
- Suspension and post insulators, spacers, dampers and other hardware
- Insulator string assemblies including tangent suspension, V-string, and dead-end assemblies
- Instrument transformers (VTs, CTs, CCVTs)

KEY LABORATORY CAPABILITIES

Effective 765 kV qualification requires voltage generation, clearances, instrumentation, and environmental controls sized specifically for ultra-high-voltage equipment.
Key capability areas of Powertech's High Voltage Laboratory include power-frequency withstand, impulse performance, partial-discharge diagnostics, corona/RIV evaluation, and controlled wet testing. These capabilities are supported by purpose built infrastructure and calibrated measurement systems, reflecting the scale, rigor, and technical controls required to perform representative and defensible 765 kV qualification testing.

1.2 MV	3.2 MV	<5 pC	<0.5 pC
Power-frequency withstand (dry/wet)	Lightning impulse peak, 1.2/50 µs	Partial-discharge sensitivity at 750 kV	Shielded background noise floor

- Power-frequency withstand testing under dry and wet conditions, with voltage sources capable of reaching 1.2 MV.
- Lightning impulse testing using a multi-stage Marx generator producing standard 1.2/50 µs waveforms up to 3.2 MV peak; switching impulse testing producing 250/2500 µs waveforms up to 2 MV peak to simulate transient overvoltage.
- PD testing up to 765 kV with sensitivity below 5pC; shielded design supports low background noise (below 0.5 pC) for reliable detection of early-stage insulation defects.
- Corona and RIV testing up to 765kV to support electromagnetic performance and interference requirements.
- Short-time withstand current tests up to 65 kArms, and temperature-rise tests up to 10 kArms single phase.
- Purpose-built laboratory facility to accommodate fully assembled EHV equipment while maintaining required electrical clearances from walls, ground and ceiling.
- Ability to support multi-conductor testing with spacers, dampers and other hardware.
- Environmental simulation for wet testing (artificial rain), humidity control, and temperature conditioning to evaluate performance across expected service conditions.
- Tensile load and proof testing of specimens up to 58 ft (17.9 m) long, with load capacities up to 500,000 lbf (2,220 kN).

- Cantilever testing of specimens up to 14 ft (4.3 m) with load capacities up to 65,000 lbf.
- Conductor stress-strain and creep testing using a 450,000 lbf (2,000 kN) test frame, generating data for PLS-CADD modeling and transmission line simulations.
- Calibration and quality systems aligned to ISO 17025 at EHV levels, including documented measurement uncertainty for critical voltage, current, and timing parameters.
- Comprehensive measurement of environmental factors to compensate test voltages and timing.
- Specialized and appropriate instrumentation, imaging and recording tools to observe and document visible corona under controlled conditions.
- An experienced test engineering team capable of distinguishing test-setup influences from true equipment performance and effectively troubleshooting anomalies.

KEY CONSIDERATIONS

765 kV testing demands specialized infrastructure, experienced test engineering, and robust quality systems beyond the reach of many conventional high-voltage laboratories. Extreme electrical stress, large physical dimensions, and stringent measurement requirements mean that both test setup and the measuring system must be capable of producing reliable, repeatable, traceable results. Early alignment between stakeholders is therefore essential to ensure successful qualification outcome.

Planning a 765 kV qualification program or evaluating lab partners for an upcoming uprate? Our team can help you scope the test plan, align it to your governing standards, and build a schedule that avoids late-stage surprises- contact us below to start the conversation.

FOR MORE INFORMATION, CONTACT:

Powertech Labs Inc.

sales@powertechlabs.com

+1.604.590.7500

ABOUT POWERTECH LABS

Powertech Labs is a leading engineering and testing organization supporting the safe and reliable development and deployment of energy infrastructure. Powertech provides independent testing, technical services, and integrated solutions across power systems, clean energy, and hydrogen technologies. Powertech work is grounded in deep technical expertise, objectivity, and a commitment to shaping the future of energy.

The Power of Trust. **The Future of Energy.**